## CHITALDROOG DIVISION.

NOTIFICATION.

*The 29th November* 1886.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldroog Division, up to 15th December 1886 for restoring the Amblagere Tank, Registered No. 12 of Hiriyur Taluk.

An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1888.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldroog between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

| Description of Work. | Unit of work. | Rate per Unit. |
|---|---|---|
| *Bund.*—Earth-work .. .. | Cubic yards 31,827. | |
| Old stone work .. .. | Cubic yards 632. | |
| New stone work .. .. | Cubic yards 1,898. | |
| Grade stones .. .. | No. 19. | |
| Fixing 2 B. M. and 16 grade stones already made | L. S. Rs. 3. | |
| *Sluices.*—No. 2 earth-work .. .. | Cubic yards 335. | |
| Brick in chunam .. .. | Cubic feet 1,149. | |
| Burnt slab stones .. .. | Square feet 269. | |
| Plastering .. .. | Square 4. | |
| Gauge stones including cutting .. | L. S. Rs. 7. | |
| Cutting crifice stones and fixing old gibbet stones | Lump sum Rs. 5. | |
| *Waste Weirs.*— | | |
| Brick in chunam .. .. | Cubic feet 2,731. | |
| Rough stone work .. .. | New cubic yards 318. | |
| Pin stones of 3' in length . .. | Square feet 720. | |
| Coping burnt stones.. .. | Square feet 363. | |

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money, and be superscribed tenders for restoring Amblagere Tank, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Secretary, Public Works Department, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

J. B. CHALON,
*Offg. Executive Engineer.*